IMC Professional Building Clean Up

Quote

Quote Number	0225
Quote Date	October 19, 2018
Valid Until	April 17, 2019
Total	**$3,250.00**

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

To:
Travis
tjslunaker@icloud.com

1969 Orange Ave, Costa Mesa CA

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the following work:
NOTE: This job will be complete in 5 business days

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Polish concrete floor in guest house garage to a 800 level grit Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two.	$3,250.00	0.00%	$3,250.00

Sub Total	$3,250.00
Tax	$0.00
Total	**$3,250.00**

The above job description outlines the services for which IMC will be responsible. These services are mutually

Approved By:_____

agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____