IMC Professional Building Clean Up

Quote

Quote Number	0289
Quote Date	December 4, 2018
Valid Until	June 2, 2019
Total	**$7,000.00**

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

To:
Alex Contractors
aochoa0546@yahoo.com

1975 Torrance Blvd, Torrance CA

We hereby propose to furnish all equipment, materials, and perform the labor necessary for the completion of the following work:

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Concrete polish 1,800sqft to a 400 grit Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two. Polish with a 400-grit resin-bond diamond. Seal concrete and buff concrete floor	$7,000.00	0.00%	$7,000.00

Sub Total	$7,000.00
Tax	$0.00
Total	**$7,000.00**

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work

Approved By:_____

IMC Professional Building Clean Up

Quote

quoted for normal business hours Monday-Friday.

Approved By:_____