IMC Professional Building Clean Up

Quote

Quote Number	0345
Quote Date	January 17, 2019
Valid Until	July 16, 2019
Total	**$12,730.00**

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

To:
Instant Flooring
hector@instantflooring.org

2367 W La Palma, Anaheim CA

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the following work:
All work is to be paid within job completion

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Patch all joints where was indicated	$550.00	0.00%	$550.00
1	Patch all holes where was indicated	$680.00	0.00%	$680.00
1	Machine scrub & seal floor	$875.00	0.00%	$875.00
2500	ALTERNATIVE to Concrete polish to 800 grit on approx 2,500sqft Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two. Polish with a 400-grit resin-bond diamond. Finish with a 800-grit resin-bond diamond. Seal concrete and buff concrete floor	$4.25	0.00%	$10,625.00

Sub Total	$12,730.00

Approved By:_____

IMC Professional Building Clean Up

Quote

Tax	$0.00
Total	**$12,730.00**

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____