IMC Professional Building Clean Up

Quote

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

Quote Number	1219
Quote Date	May 13, 2020
Valid Until	November 9, 2020
Total	**$11,749.00**

To:
Constumer D. Saint Mojica
11055 Molette St, Norwalk CA 9065
ugotsaint@hotmail.com

11055 Molette St, Norwalk CA

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the following work
OPTION 1

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Demo existing concrete and haul away debris off site	$1,100.00	0.00%	$1,100.00
1	Pour in new concrete in front drive way approx 807sqft by 4inches includes all material and labor Preparation: expose raw earth, form wood set, install 1/2 rebar in a 2 grit pattern, pour ready mix concrete 3,500 PSI, screed concrete to compact troweling and final finish.	$6,349.00	0.00%	$6,349.00
1	Pour in new concrete in backyard approx 506sqft by 4inches includes all material and labor Preparation: expose raw earth, form wood set, install 1/2 rebar in a 2 grit pattern, pour ready mix concrete 3,500 PSI, screed concrete to compact troweling and final finish.	$4,300.00	0.00%	$4,300.00

Approved By:_____

IMC Professional Building Clean Up

Quote

Sub Total	$11,749.00
Tax	$0.00
Total	**$11,749.00**

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____