# IMC Professional Building Clean Up

# Quote

| | |
|---|---|
| Quote Number | 0979 |
| Quote Date | January 16, 2020 |
| Valid Until | July 14, 2020 |
| **Total** | **$19,101.50** |

**From:**
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

**To:**
CMD Construction
9272 Jeronimo Road, Suite 102,
Irvine, CA 92618
michael@cmdconstructioninc.com

3525 W Carson St, Torrance, CA

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the following work
**During work hours**

| Hrs/Qty | Service | Rate/Price | Adjust | Sub Total |
|---|---|---|---|---|
| 3682 | Concrete polish to level 3 (800 grit) on 3,682sqft<br>Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two. Polish with a 400-grit resin-bond diamond. Finish with a 800-grit resin-bond diamond. Seal concrete and buff concrete floor | $4.25 | 0.00% | $15,648.50 |
| 1 | ALTERNATIVE to demo VCT floors on 3,682sqft | $2,025.00 | 0.00% | $2,025.00 |
| 1 | ALTERNATIVE to remove glue on 3,682sqft | $1,288.00 | 0.00% | $1,288.00 |

Approved By:_____

# IMC Professional Building Clean Up

Quote

| Hrs/Qty | Service | Rate/Price | Adjust | Sub Total |
|---|---|---|---|---|
| 1 | ALTERNATIVE to remove base on 700sqft | $140.00 | 0.00% | $140.00 |

| | |
|---|---|
| Sub Total | $19,101.50 |
| Tax | $0.00 |
| **Total** | **$19,101.50** |

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____