IMC Professional Building Clean Up

Quote

Quote Number	0323
Quote Date	January 3, 2019
Valid Until	July 2, 2019
Total	**$17,080.00**

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

To:
Garvey School District
2730 Del Mar Ave, Rosemead, CA
alacaraz.edward@yahoo.com

7830 Dorothy St, Rosemead CA

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the fallowing work:

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
4627	Remove existing sealer from floor and grind starting from 20-30 grit to 200grit and concrete polish to 800grit and apply stain and clear coat based on 4,627sqft	$2.75	0.00%	$12,724.25
917	Concrete polish floor to 800 grit and apply stain (color chosen by costumer) Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two. Polish with a 400-grit resin-bond diamond. Finish with a 800-grit resin-bond diamond. Seal concrete and buff concrete floor	$4.75	0.00%	$4,355.75

Approved By:_____

IMC Professional Building Clean Up

Quote

Sub Total	$17,080.00
Tax	$0.00
Total	**$17,080.00**

Approved By:_____

IMC Professional Building Clean Up

Quote

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____