IMC Professional Building Clean Up

Quote

Quote Number	0622
Quote Date	June 12, 2019
Valid Until	December 9, 2019
Total	**$23,649.50**

From:
IMC Professional Building Clean Up
12155 Magnolia Avenue Unit 10-E,
Riverside, CA 92503
Phone: (951) 279-7705
Email: ema@imccleanup.com
CSLB Lic # 962294

To:
VP-Build
peter@vp-build.com

Huntington Beach

We hereby propose to furnish all equipment and materials, and perform the labor necessary for the completion of the following work:
Work is to be done during regular hours

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Concrete polish to level 3 (800 grit) on 3,363sqft Grind new concrete with a 30- or 40-grit metal-bonded diamond, Grind with an 80-grit metal-bonded diamond, Grind with a 150-grit metal-bonded diamond (or finer, if desired). Apply a chemical hardener to densify the concrete. Polish with a 100-grit or 200-grit resin-bond diamond, or a combination of the two. Polish with a 400-grit resin-bond diamond. Finish with a 800-grit resin-bond diamond. Seal concrete and buff concrete floor	$14,683.50	0.00%	$14,683.50
1	Prep floor to apply epoxy color chosen by costumer on 2,391sqft	$8,966.00	0.00%	$8,966.00

Sub Total	$23,649.50
Tax	$0.00

Approved By:_____

IMC Professional Building Clean Up

Quote

Total	**$23,649.50**

The above job description outlines the services for which IMC will be responsible. These services are mutually agreed to be appropriate for your needs at this time, all change orders must be submitted in written. Work quoted for normal business hours Monday-Friday.

Approved By:_____